



PERITUS
SKILLED IN THE ART OF ENGINEERING

Tri-County
Wilson Hall – HVAC RTU Replacement
Project # CUP 4002758/CAP 2221

Addendum No. 2

DATE: November 21, 2022
FROM: PERITUS ENGINEERS & ASSOCIATES, INC.
TO: ALL BIDDERS

The following items add to, modify, clarify, or otherwise alter the Drawings and/or specifications and will become a part of the Contract Documents. Where a portion of the Drawings and/or specifications is added to, modified, clarified, or otherwise altered, the portion not so affected shall remain. Bidder shall include all effects that these items may have on his proposal.

Questions received before 11-21-22:

1. The following note shall be added to the "Natural Gas Piping Detail on drawing M-3.

"It has been determined that the existing 3" gas pipe main is steel pipe and coated with bituminous tar wrap. The connection to the existing gas main pipe shall be with steel fitting (s) to match the existing pipe and shall be coated with similar bituminous tar wrap. Pipe fitting/coupling to convert steel pipe to Polyethylene tubing shall be installed on new connection fitting. New 1" (5 PSIG) seamless polyethylene tubing shall be installed 24" deep and extend to edge of existing building. Transition Polyethylene to Sch. 40 steel pipe above ground. "

END OF ADDENDUM NO. 2

PERITUS ENGINEERS & ASSOCIATES, INC.

P.O. Box 16598, Greenville, SC 29606 10 E. Dorchester Blvd. Greenville, SC 29605

o. 864-277-8287, f. 864-277-8290, peritus@peritusengineers.com